# BRUHATH BENGALURU MAHANAGARA PALIKE

**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/14/2017-18 Dated: 28-12-2017

## APPROVED TENDER SCHEDULE –'B'

Item No: 07

Name of Work:-Improvements to roads and drains at balaji layout in Kenchenahalli in ward No:02 of Yelahanka sub division

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri Y A DHANASHEKHAR | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRB 2-2.1 : **Earth work excavation** for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3) | Cum | 713.90 | 215.00 | Rupees Two Hundred Fifteen Only |
| 2 | KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) | Cum | 713.90 | 105.00 | Rupees One Hundred Five Only |
| 3 | KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3) | Cum | 97.35 | 5500.00 | Rupees Five Thousand Five Hundred Only |
| 4 | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC cement at 300kgs. with 20mm and down size granite metal coarse aggregates at 0.69cum and fine aggregates at 0.43cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No.1500, 1700, 2200. -do- Wall and bottom thickness 15cm (P.No.265 / It.No.37.59) | Cum | 203.55 | 11880.00 | Rupees Eleven Thousand Eight Hundred Eighty Only |

| | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri Y A DHANASHEKHAR | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| | KSRB 4.9.2: Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **-do- TMT Bars Fe 500** P.17/It.No.4.46.2 | tonne | 12.2130 | 80650.00 | Rupees Eighty Thousand Six Hundred Fifty Only |
| 6 | Providing and fixing **RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm** and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete | Sqm | 531.00 | 2259.00 | Rupees Two Thousand Two Hundred Fifty Nine Only |

Y.A. Dhanashekhar
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.